DOCUMENT RESUME

ED 468 805 SE 066 739

| | |
|---|---|
| AUTHOR | Coburn, John W. |
| TITLE | After Five Hundred Years...A Significant New Look at Quadratic Functions. |
| PUB DATE | 2000-00-00 |
| NOTE | 10p. |
| PUB TYPE | Numerical/Quantitative Data (110) -- Reports - Descriptive (141) |
| EDRS PRICE | EDRS Price MF01/PC01 Plus Postage. |
| DESCRIPTORS | *Algebra; Curriculum Development; *Graphs; Higher Education; Mathematics Education; Secondary Education; Teaching Methods; *Textbooks |
| IDENTIFIERS | *Quadratic Equations |

ABSTRACT

This paper describes "The Migration Method," a new technique for graphing a quadratic function (one of the major foundations of undergraduate mathematics) and finding its zeroes. The method promotes a higher degree of conceptualization, reinforces the concept of symmetry, encourages mental visualization, and strengthens the ability to graph a given function by translating a parent or base function. (YDS)

Reproductions supplied by EDRS are the best that can be made
from the original document.

ED 468 805

# *After Five Hundred Years ... A Significant New Look at Quadratic Functions*

## Introducing ***The Migration Method*** ...

A new approach to graphing a quadratic function and determining its zeroes, developed by

John W. Coburn
of
St. Louis Community College
at Florissant Valley

3400 Pershall Road
St. Louis, Missouri 63135
(314) 595-4343 (office)
(314) 595-2199 (facsimile)
jcoburn@stlcc.edu
©2000 John W. Coburn

PERMISSION TO REPRODUCE AND DISSEMINATE THIS MATERIAL HAS BEEN GRANTED BY

J. Coburn

TO THE EDUCATIONAL RESOURCES INFORMATION CENTER (ERIC)

1

U.S. DEPARTMENT OF EDUCATION
Office of Educational Research and Improvement
EDUCATIONAL RESOURCES INFORMATION CENTER (ERIC)

☒ This document has been reproduced as received from the person or organization originating it.

☐ Minor changes have been made to improve reproduction quality.

• Points of view or opinions stated in this document do not necessarily represent official OERI position or policy.

BEST COPY AVAILABLE

SE060739

*A Significant New Look at Quadratic Functions*

Introducing ***The Migration Method*** ...

**Introduction**

Two years ago, a contract was signed with Harcourt College Publishers for the development of a new series of textbooks in developmental mathematics (PreAlgebra through Intermediate Algebra). Writing these textbooks has been a daunting task, yet one that has provided many surprising turns and diverse rewards. I wish to share one of the more substantial "surprises" in this dialogue. Long before pen was put to paper, I made a conscious decision to present and develop the graph of a function *prior* to solving any of the related inequalities. Having always been bothered by the "blind" interval tests seen in many texts, I set about laying groundwork that might enable students to "see" solutions mentally, understand them more completely and solve inequalities with far fewer tests. Linear functions presented no challenge, as a student need only find the x intercept and consider the slope of the line. Likewise, a "visual" solution to absolute value inequalities can easily be developed from characteristics of the graph. However, this presented the challenge of discussing absolute value inequalities *before the topic of translations had been addressed.* While immersed in the consideration of this function and the characteristics of its' graph, I was struck once again by its similarity to the graph of a quadratic function. Noting particularly that the rate of change between a vertical shift of $f(x) = |x|$ and the zeroes of this function was constant, I reasoned that perhaps a similar relationship existed between a vertical shift of $f(x) = x^2$ and its zeroes. The resulting analysis has opened doors and yielded ideas that have apparently not been opened or explored previously. This paper describes a new technique for graphing a quadratic function and finding its zeroes, which I have dubbed ***The Migration Method*** for reasons that will soon be apparent.

For the quadratic function $f(x) = ax^2 + bx + c$,

the following statements are universally accepted.

① The graph of **f** is a parabola

② The parabola is concave up if $a > 0$; concave down if $a < 0$

③ The axis of symmetry is $x = -\frac{b}{2a}$

④ The vertex is at $\left(-\frac{b}{2a}, f(-\frac{b}{2a})\right)$

⑤ The y intercept is at (0, c) with $(-\frac{b}{a}, c)$ as a point of symmetry

⑥ The x intercepts are $(\frac{-b-\sqrt{b^2-4ac}}{2a}, 0)$ and $(\frac{-b+\sqrt{b^2-4ac}}{2a}, 0)$

Let us consider $F(x) = ax^2 + bx$ as the **base function** of $f(x) = ax^2 + bx + c$, or the original function less the constant term. Four things are immediately apparent: ① **F** and **f** share the same axis of symmetry, ② the zeroes of **F** are easily found, ③ the axis of symmetry can be determined mentally, and ④ the vertices of **F** and **f** differ only by the constant c. Consider these vertices to be $(h, k_0)$ and $(h, k)$ respectively, with $k = k_0 + c$.



**Claim:** The vertex of F can alternatively be given as $(h, k_o) \rightarrow (h, -ah^2)$.

**Proof:** Note that for F: ① The x intercepts are (0, 0) and $(-\frac{b}{a}, 0)$

② the axis of symmetry is halfway between these points, $h = -\frac{b}{2a}$.

Since the vertex must lie on the axis of symmetry,

③ the x coordinate of the vertex is $h = -\frac{b}{2a}$ and the y coordinate is $k_o = F(-\frac{b}{2a})$.

As shown below, the expression $F(-\frac{b}{2a})$ is equivalent to $-a\left(\frac{b}{2a}\right)^2$:

$$F(x) = ax^2 + bx \qquad \text{original function}$$

$$F(-\tfrac{b}{2a}) = a(-\tfrac{b}{2a})^2 + b(-\tfrac{b}{2a}) \qquad \text{substitute } x = -\tfrac{b}{2a}$$

$$= \frac{b^2}{4a} - \frac{b^2}{2a}$$

$$= \frac{b^2 - 2b^2}{4a}$$

$$= \frac{-b^2}{4a} \qquad \text{simplify}$$

$$= \frac{-b^2}{4a} \cdot \frac{a}{a} \qquad \text{multiply by } \tfrac{a}{a}$$

$$= -a\left(\frac{b}{2a}\right)^2 \qquad \text{result}$$

From $h = -\frac{b}{2a}$ we have $-h = \frac{b}{2a}$ and it follows that

$$F(-\tfrac{b}{2a}) = -a(-h)^2 \qquad \text{substitute } -h = \tfrac{b}{2a}$$

$$= -ah^2 \qquad (-h)^2 = h^2$$

This verifies $k_o = -ah^2$. The vertex of F is $(h, k_o) \rightarrow (h, -ah^2)$ as claimed. ◆

It is very significant to note that the vertex of both F(x) and f(x) *can now be determined using elementary operations on the single value h*, since $k_0 = -ah^2$ and $k = k_0 + c$. In other words, the vertex of the original function can be found by shifting or migrating the base function (i.e. the original function less its constant term). This is all the more valuable in that h itself can be found ***mentally*** – it is the point halfway between the x intercepts. In light of my original goal stated in the first paragraph (the solution of function inequalities) it seemed natural to next consider the effect this vertical migration had on the x-intercepts of the original function **f**.

**Claim:** The x-intercepts (zeroes) of **f** are $x = h + \sqrt{-\frac{k}{a}}$ and $x = h - \sqrt{-\frac{k}{a}}$.

**Proof:** The zeroes of **f** are the solutions of $ax^2 + bx + c = 0$. Solve by completing the square:

| | | | |
|---|---|---|---|
| $x^2 + \frac{b}{a}x + \frac{c}{a}$ | = | $0$ | divide by leading coefficient |
| $x^2 + \frac{b}{a}x + \left(\frac{b}{2a}\right)^2$ | = | $\left(\frac{b}{2a}\right)^2 - \frac{c}{a}$ | add $\left(\frac{b}{2a}\right)^2$ to each side |
| $(x + \frac{b}{2a})^2$ | = | $\left(\frac{b}{2a}\right)^2 - \frac{c}{a}$ | left side factors as a binomial square |
| $(x - h)^2$ | = | $(-h)^2 - \frac{c}{a}$ | substitute $\frac{b}{2a} = -h$ |
| $(x - h)^2$ | = | $h^2 - \frac{c}{a}$ | $(-h)^2 = h^2$ |
| $(x - h)^2$ | = | $-\frac{k_0}{a} - \frac{c}{a}$ | substitute $-\frac{k_0}{a} = h^2$ (from $k_0 = -ah^2$) |
| $(x - h)^2$ | = | $\frac{-(k_0 + c)}{a}$ | combine terms |
| $(x - h)^2$ | = | $-\frac{k}{a}$ | substitute $k_0 + c = k$ |
| $x - h$ | = | $\pm\sqrt{-\frac{k}{a}}$ | solve for x |
| $x$ | = | $h \pm \sqrt{-\frac{k}{a}}$ | ***Richard's Formula*** (see final notes) |

This shows the zeroes of **f** are $x = h + \sqrt{-\frac{k}{a}}$ and $x = h - \sqrt{-\frac{k}{a}}$ as claimed. ◆

**A startling result ...**

A complete graph of $f(x) = ax^2 + bx + c$ can now be drawn by (mentally) migrating its base function and locating the zeroes as shown. The efficiency of this graphing alternative (***The Migration Method***) and the significance of its simplicity cannot be overstated -- as it circumvents the need to manipulate the function and increases an understanding of both symmetry and shifts. Using the method in conjunction with ***Richard's Formula*** bypasses the (student's) difficulties in using the quadratic formula, making all aspects of the quadratic function more accessible with no compromise in the integrity of the curriculum and no damage to the science or art of mathematics. In addition, it opens up a wonderful opportunity to discuss exact forms versus approximate forms.

The main ideas are summarized here, followed by several examples. For the quadratic function $f(x) = ax^2 + bx + c$ and the "base function" $F(x) = ax^2 + bx$, the axis of symmetry is $-\frac{b}{2a} = h$ and ...

| | x-intercepts | vertex | y-intercept | point of symmetry |
|---|---|---|---|---|
| For **F**: | $(0, 0)$ and $(-\frac{b}{a}, 0)$ | $(h, -ah^2)$ $(h, k_o)$ | $(0, 0)$ | $(-\frac{b}{a}, 0)$ |
| For **f**: | (see below) | $(h, k_o + c)$ | $(0, c)$ | $(-\frac{b}{a}, c)$ |
| | | add "c" $(h, k_o + c) \rightarrow (h, k)$ | add "c" | add "c" |

The x intercepts of **f** (found after locating the vertex) are given by $(h \pm \sqrt{-\frac{k}{a}}, 0)$.

Note that the y intercept and one x-intercept of **F** coincide at (0, 0). The other x-intercept can be found by inspection (since the first is at the origin). These x-intercepts can also be viewed as *the y-intercept and a point which is symmetric to the y-intercept*, reinforcing the concept of symmetry and making this point of symmetry easy (almost trivial) to find for both **F** and **f**. We begin with an example where $a = 1$ and b is an even integer. This simplifies our work even further, yielding $k_o = -h^2$ with the x-intercepts of **f** at $x = h \pm \sqrt{-k}$. *The actual graphs are left for the reader to construct, only the vital information is presented here.*

Example 1: Graph the function $f(x) = x^2 - 10x + 17$ and locate its zeroes (if they exist).

solution: For $F(x) = x^2 - 10x$, the zeroes are (0, 0) and (10, 0) by inspection, with **h = 5** (halfway point) as the axis of symmetry. Note **a = 1** and **c = 17**. It follows that:

| | x-intercepts | vertex | y-intercept | point of symmetry |
|---|---|---|---|---|
| For **F**: | (0, 0) and (10, 0) | (5, -25)<br>$(h, -h^2)$ | (0, 0) | (10, 0) |
| For **f**: | (see below) | (5, -8)<br>(h, k)<br>$k = k_0 + 17$ | (0, 17)<br>add 17 | (10, 17)<br>add 17 |

Since a = 1 and k = -8, the x intercepts of **f** are given by $(5 \pm \sqrt{8}, 0)$.
$(h \pm \sqrt{-k}, 0)$

If b is an odd number, there is no significant increase in difficulty when computing the "halfway point", since for any integer z we know that $(z.5)^2 = |z|(|z| + 1).25$. For instance, $(6.5)^2 = 6(6 + 1).25$ or 42.25, and $(-3.5)^2 = 3(3 + 1).25$ or 12.25.

Example 2: Graph the function $f(x) = x^2 + 13x - 15$ and locate its zeroes (if they exist).

solution: For $F(x) = x^2 + 13x$, the zeroes are (0, 0) and (-13, 0) by inspection, with **h = -6.5** as the axis of symmetry. Note **a = 1** and **c = -15**. It follows that:

| | x-intercepts | vertex | y-intercept | point of symmetry |
|---|---|---|---|---|
| For **F**: | (0, 0) and (-13, 0) | (- 6.5, - 42.25)<br>$(h, -h^2)$ | (0, 0) | (-13, 0) |
| For **f**: | (see below) | (- 6.5, - 57.25)<br>(h, k)<br>$k = k_0 + (-15)$ | (0, -15)<br>add -15 | (-13, -15)<br>add -15 |

Since a = 1 and k = -57.25, the x intercepts of **f** are given by $(-6.5 \pm \sqrt{57.25}, 0)$.
$(h \pm \sqrt{-k}, 0)$

Even when $a \neq 1$, the *Migration Method* is more efficient than methods currently employed since virtually every step can still be done mentally – even when students or instructors choose to work with rational values.

Example 3: Graph the function $f(x) = 2x^2 + 7x - 10$ and locate its zeroes (if they exist).

solution: For $F(x) = 2x^2 + 7x$, the zeroes are (0, 0) and $(-\frac{7}{2}, 0)$, with $h = -\frac{7}{4}$ as the axis of symmetry. Note $a = 2$ and $c = -10$. It follows that:

| | x-intercepts | vertex | y-intercept | point of symmetry |
|---|---|---|---|---|
| For F: | (0, 0) and $(-\frac{7}{2}, 0)$ | $(-\frac{7}{4}, -\frac{49}{8})$ $(h, -ah^2)$ | (0, 0) | $(-\frac{7}{2}, 0)$ |
| For f: | (see below) | $(-\frac{7}{4}, -\frac{129}{8})$ (h, k) $k = k_o + (-10)$ | (0, -10) add -10 | $(-\frac{7}{2}, -10)$ add -10 |

Since $a = 2$ and $k = -\frac{129}{8}$, the x intercepts of f are given by $(-\frac{7}{4} \pm \sqrt{\frac{129}{16}}, 0)$. $(h \pm \sqrt{-\frac{k}{a}}, 0)$

The final result can be simplified to $\frac{-7 \pm \sqrt{129}}{4}$.

One of the more remarkable benefits of determining the zeroes using *Richard's Formula*, comes when the roots of the function are complex, as in Example 4.

Example 4: Graph the function $f(x) = -2x^2 + 9x - 12$ and locate its zeroes (if they exist).

solution: For $F(x) = -2x^2 + 9x$, the zeroes are (0, 0) and $(\frac{9}{2}, 0)$ by inspection, with $h = \frac{9}{4}$ as the axis of symmetry. Note $a = -2$ and $c = -12$. It follows that:

| | x-intercepts | vertex | y-intercept | point of symmetry |
|---|---|---|---|---|
| For F: | (0, 0) and $(\frac{9}{2}, 0)$ | $(\frac{9}{4}, \frac{81}{8})$ $(h, -ah^2)$ | (0, 0) | $(\frac{9}{2}, 0)$ |
| For f: | (see below) | $(\frac{9}{4}, -\frac{15}{8})$ (h, k) $k = k_o + (-12)$ | (0, – 12) add -12 | $(\frac{9}{2}, -12)$ add -12 |

The complex roots of f are $x = \frac{9}{4} \pm \sqrt{-\frac{15}{16}}$ $(x = h \pm \sqrt{-\frac{k}{a}})$,

which simplifies to $x = \frac{9}{4} \pm \frac{\sqrt{15}}{4} i$.

Since a and k have like signs, the radicand of $\sqrt{-\frac{k}{a}}$ is negative and there are no real roots. Talk about connections! The radicand is explicitly telling a student that if the graph is concave up with k positive ($a > 0$ and $k > 0$), or if the graph is concave down with k negative ($a < 0$ and $k < 0$), the result is an imaginary number and *there are no x intercepts*. This conceivably antiquates the "old" discriminant $b^2 - 4ac$ while explicitly stating a link between characteristics of the graph and the nature of its zeroes.




In summary, I believe the Migration Method opens an exciting new chapter in the study of quadratic functions – one of the major foundations of undergraduate mathematics. The method promotes a higher degree of conceptualization, reinforces the concept of symmetry, encourages mental visualization and strengthens the ability to graph a given function by translating a parent or base function. Additionally, I believe the method will lead to a quicker solution and a better understanding of quadratic and other inequalities.

**Final Note**

I've named this new formula for solving a quadratic ***Richard's Formula***, in honor of my father. As an instructor of mathematics, there were few who were his equal.

SE066739

**U.S. Department of Education**
*Office of Educational Research and Improvement (OERI)*
*National Library of Education (NLE)*
*Educational Resources Information Center (ERIC)*

# REPRODUCTION RELEASE

(Specific Document)

## I. DOCUMENT IDENTIFICATION:

| | |
|---|---|
| Title: After 500 Years... A Significant New Look at Quadratic Functions | |
| Author(s): John W. Coburn | |
| Corporate Source: — | Publication Date: |

## II. REPRODUCTION RELEASE:

In order to disseminate as widely as possible timely and significant materials of interest to the educational community, documents announced in the monthly abstract journal of the ERIC system, *Resources in Education* (RIE), are usually made available to users in microfiche, reproduced paper copy, and electronic media, and sold through the ERIC Document Reproduction Service (EDRS). Credit is given to the source of each document, and, if reproduction release is granted, one of the following notices is affixed to the document.

If permission is granted to reproduce and disseminate the identified document, please CHECK ONE of the following three options and sign at the bottom of the page.

| The sample sticker shown below will be affixed to all Level 1 documents | The sample sticker shown below will be affixed to all Level 2A documents | The sample sticker shown below will be affixed to all Level 2B documents |
|---|---|---|
| PERMISSION TO REPRODUCE AND DISSEMINATE THIS MATERIAL HAS BEEN GRANTED BY<br>Sample<br>TO THE EDUCATIONAL RESOURCES INFORMATION CENTER (ERIC)<br>1 | PERMISSION TO REPRODUCE AND DISSEMINATE THIS MATERIAL IN MICROFICHE, AND IN ELECTRONIC MEDIA FOR ERIC COLLECTION SUBSCRIBERS ONLY, HAS BEEN GRANTED BY<br>Sample<br>TO THE EDUCATIONAL RESOURCES INFORMATION CENTER (ERIC)<br>2A | PERMISSION TO REPRODUCE AND DISSEMINATE THIS MATERIAL IN MICROFICHE ONLY HAS BEEN GRANTED BY<br>Sample<br>TO THE EDUCATIONAL RESOURCES INFORMATION CENTER (ERIC)<br>2B |
| Level 1 | Level 2A | Level 2B |
| ✓ Check here for Level 1 release, permitting reproduction and dissemination in microfiche or other ERIC archival media (e.g., electronic) and paper copy. | Check here for Level 2A release, permitting reproduction and dissemination in microfiche and in electronic media for ERIC archival collection subscribers only | Check here for Level 2B release, permitting reproduction and dissemination in microfiche only |

Documents will be processed as indicated provided reproduction quality permits.
If permission to reproduce is granted, but no box is checked, documents will be processed at Level 1.

*I hereby grant to the Educational Resources Information Center (ERIC) nonexclusive permission to reproduce and disseminate this document as indicated above. Reproduction from the ERIC microfiche or electronic media by persons other than ERIC employees and its system contractors requires permission from the copyright holder. Exception is made for non-profit reproduction by libraries and other service agencies to satisfy information needs of educators in response to discrete inquiries.*

| | |
|---|---|
| Signature: John W. Coburn | Printed Name/Position/Title: John W Coburn Professor of Math |
| Organization/Address: | Telephone: 314-595-4343 FAX: 314-595-2199 |
| | E-Mail Address: jcoburn@stlcc.edu Date: 8/23/02 |

stlcc.edu

## III. DOCUMENT AVAILABILITY INFORMATION (FROM NON-ERIC SOURCE):

If permission to reproduce is not granted to ERIC, *or*, if you wish ERIC to cite the availability of the document from another source, please provide the following information regarding the availability of the document. (ERIC will not announce a document unless it is publicly available, and a dependable source can be specified. Contributors should also be aware that ERIC selection criteria are significantly more stringent for documents that cannot be made available through EDRS.)

| |
|---|
| Publisher/Distributor: |
| Address: |
| Price: |

## IV. REFERRAL OF ERIC TO COPYRIGHT/REPRODUCTION RIGHTS HOLDER:

If the right to grant this reproduction release is held by someone other than the addressee, please provide the appropriate name and address:

| |
|---|
| Name: |
| Address: |

## V. WHERE TO SEND THIS FORM:

| |
|---|
| Send this form to the following ERIC Clearinghouse: |

However, if solicited by the ERIC Facility, or if making an unsolicited contribution to ERIC, return this form (and the document being contributed) to:

**ERIC Processing and Reference Facility**
**4483-A Forbes Boulevard**
**Lanham, Maryland 20706**

**Telephone: 301-552-4200**
**Toll Free: 800-799-3742**
**FAX: 301-552-4700**
**e-mail: ericfac@inet.ed.gov**
**WWW: http://ericfacility.org**